

[illegible]

CYLINDERS-----17'x24"  
 " SPREAD,-----84"  
 TUBES, NUMBER,-----144  
 " OUT. DIA.-----2"  
 " LENGTH BET. SHEETS, 128'<sup>3</sup>/<sub>4</sub>  
 FIREBOX, SIZE OF INSIDE, 34½'x55'<sup>1</sup>/<sub>2</sub>  
 HEATING SUR. TUBES, 809.75 SQ. FT.

HEATING SUR. FIREBOX, --- 90.10 SQ. FT.  
 " " TOTAL, --- 899.85 " "  
 STEAM PRESSURE, --- 160 LBS.  
 WT. OF ENG. EMPTY, --- 72500 "  
 " ON DRIVERS " --- 72500 "  
 " OF ENG. WORKING ORDER, --- 200 "  
 " ON 2 DRIVERS WORKING ORDER, 36700.

WT. ON 2<sup>ND</sup> DRIVERS, WORKING ORDER, 43500 LBS.  
TENDER, WT. LOADED, ----- 61150 "  
" CAPACITY, WATER, ----- 2700 GALS.  
" " COAL, ----- 7700 LBS.