



HEATING SUR FIREBOX:-----93 SQ.FT.

WT.ON 14 DRIVERS,WORKING ORDER 32800 LBS.

.. " TOTAL-----1256 .. "

" " QND " " " 32500 "

STEAM PRESSURE ----- 160 LBS

• " TRUCK " " 38200 "

WT. OF ENG. EMPTY, ---- 93050 ..

TENDER, WT. LOADED,-----79950 "

.. ON DRIVER6 .. -----58550 ..

.. CAPACITY WATER --- 9600 GALS.

.. .. TRUCK .. - - - - - 34500 ..

COAL,----15000LBS

.. OF ENG WORKING ORDER 103600 ..

.. FITTED WITH SCOOP