

[illegible]

WIDTH OF CAB ROOF,-----	9' - 10
" " "-----	9' - 4
HEIGHT " " " FROM RAIL	13' - 9
INSIDE LENGTH OF FIREBOX,--	10' - 0 ³ / ₁₆
" WIDTH " "-----	2' - 9 ⁸ / ₁₆
TUBES, NUMBER-----	270
" LENGTH-----	14' - 0
" OUT. DIA.-----	2
WT. OF ENG. EMPTY	

WT. ON DRIVERS,
 " " TRUCK,
 " OF ENG. WORKING ORDER,
 " ON 1ST DRIVERS ----- 33800 LBS.
 " " 2ND " ----- 35500 "
 " " 3RD " ----- 32000 "
 " " TRUCK ----- 38000 "
 TOTAL WT. WORKING ORDER 132 000